

SYSTEM SPECIFICATION.

- (1) MRC Liner Sheet or existing roof sheeting as per specification.
- (2) Ashgrid Bar & Bracket Spacer Support System with Thermal Pad & Fixings as per specification.
- (3) Optional Thermal Insulation as per specification, if not used then a MRC Breather Membrane to be installed between the Ashgrid and the 'Secret Fix' Clip.
- (4) MRC 'Pierced Fix' Roof Sheeting as per specification.
- (5) Ridge Serrated Metal Closure as per specification.
- (6) Ridge Polyclosure complete with mastic seal as per specification.
- (7) 'Turn Up' off the MRC 'Pierced Fix' Roof Sheeting as per specification.
- (8) Headwall Flashing complete with angled metal counter flashing as per specification.



MRC Systems (PTY) Ltd

Offices: Johannesburg, Durban, Cape Town

This drawing is copyright and is issued on the express condition that it is not to be copied or disclosed by or to any unauthorised person or firms without prior consent in writing from MRC Group.

GENERAL NOTES.

- 1). Do not scale from this drawing
- 2). All dimensions shown on this drawing are in millimetres (mm) and are nominal unless marked.
- 3). Isolate all interfaces between dissimilar materials.
- 4). All details backed by the 'Guardian' System Warranty.

Drawing Title Project: Headwall MRC Group 'Plerced Flx"

to Brickwork Buit Up Roof Construction With Liner Sheet

Drawn MRC Date: 08/2015 Scale: 1:5 @ A3 Check:

Drawing No.: MRC/FR/PF/PDHW/BU/DWG001